



SOUTH AUSTRALIAN WATER CORPORATION

TECHNICAL STANDARD

THE SUPPLY OF 305 mm DIAMETER WELDED STEEL VENT TUBES (TS 12 & TS 97 accompany this TS)



Issued by:

Standards Manager Networks Infrastructure

Issue Date:

10 January 2007



© **SA WATER 2007**

This is an intellectual property of the South Australian Water Corporation. This document is copyright and all rights are reserved by SA Water. No part may be reproduced, copied or transmitted in any form or by any means without the express written permission of SA Water.

The information contained in these Standards is strictly for the private use of the intended recipient in relation to works or projects of SA Water.

These Standards have been prepared for SA Water's own internal use and SA Water makes no representation as to the quality, accuracy or suitability of the information for any other purpose.

It is the responsibility of the users of these Standards to ensure that the application of information is appropriate and that any designs based on these Standards are fit for SA Water's purposes and comply with all relevant Australian Standards, Acts and regulations. Users of these Standards accept sole responsibility for interpretation and use of the information contained in these Standards.

SA Water and its officers accept no liability for any loss or damage caused by reliance on these Standards whether caused by error, omission, misdirection, misstatement, misinterpretation or negligence of SA Water.

Users should independently verify the accuracy, fitness for purpose and application of information contained in these Standards.

The currency of these Standards should be checked prior to use.

APPROVAL TO DEVIATE FROM THIS STANDARD

Approval may be granted by the Asset Owner to deviate from the requirements as stipulated in this Standard if the functional requirements (e.g. Asset Life) for the asset differs from those stated in the Standard, but is assessed as still being acceptable by the Asset Owner's nominated representative.

Any approval to deviate from the stated requirements of this Standard will not be seen as creating a precedent for future like project. Any request to deviate from this Standard must be carried out on a project by project basis where each alternate proposal will be individually assessed on its own merit.

NO CHANGES REQUIRED IN THE JANUARY 2007 EDITION

The following lists the major changes to the September 2002 edition and published in the September 2004 edition of TS 55:

- 1. Reformatted from DS to TS (Departmental Standard to Technical Standard), and updated referenced Australian Standards.
- 2. Conversion to a technical standard by removal of contractual conditions (to be included in the contract that references this specification).
- 3. Corrected Title to 305 mm not 350 mm.

SA Water	TS55 - Vent-Tubes_2.docx	10 January 2007	Page
PLANNING & INFRASTRUCTURE	Issued by: Standards Manager Networks Infrastructure	Uncontrolled on printing	2 of 6

CONTENTS

© SA WATER 2007	2
© 54 WAILR 2007	. 2
APPROVAL TO DEVIATE FROM THIS STANDARD	. 2
NO CHANGES REQUIRED IN THE JANUARY 2007 EDITION	. 2
CONTENTS	. 3
REFERENCED DOCUMENTS	. 3
SECTION 1: GENERAL	. 4
SECTION 2: MATERIALS	. 4
2.1 Steel	. 4
2.2 Coating Materials	. 4
SECTION 3: MANUFACTURE	. 4
SECTION 4: COATING	. 4
4.1 Surface Preparation	. 4
4.2. Coating Application	. 5
4.2.1 External Surface	. 5
4.2.2 Internal Surface	. 5
4.2.3 Coating Inspection.	. 5
SECTION 5: QUALITY CONTROL AND ASSURANCE	. 5
APPENDIX A REFERENCE DRAWING	. 6

REFERENCED DOCUMENTS

AS/NZS 1554:	Structural Steel Welding	
AS 1579:	Arc-welded steel pipes and fittings for water and waste-water	
AS 3768:	Guide to the effects of temperature on electrical equipment	
AS 3894:	Site testing of protective coatings	
AS/NZS ISO 9001:	Quality management systems – Requirements	
Drawing No. 94-0168-03A: Page J3 in the Sewer Construction Manual Drawings		
TS 12	Surface Preparation and Protection of Steelwork Using an Inorganic Zinc	
	Silicate Coating	
TS 54	Supply of Steel Vent Tube Bases and Vent Base Holding Down Bolts	
	(TS 84 accompanies this TS)	
TS 97	Surface Preparation and Protection of Steelwork Using Potable Water	
	Approved Epoxy High Build 2-Pack Solventless	

PLANNING & INFRASTRUCTURE	TS55 - Vent-Tubes_2.docx	10 January 2007	Page
	Issued by: Standards Manager Networks Infrastructure	Uncontrolled on printing	3 of 6

SECTION 1: GENERAL

This Technical Standard covers the fabrication of steel vent tubes. These vent tubes are assembled with the vent tube bases (to TS 54) as shown in TS 54 and on Drawing 94-0168-03A (Shown in Appendix A - Reference Drawing).

SA Water Technical Standard's (TS's) 12 and 97 accompany this TS.

SECTION 2: MATERIALS

2.1 Steel

The steel plate shall be Grade 250 in accordance with AS 3678.

2.2 Coating Materials

Coatings shall be in accordance with TS 12 and TS 97.

SECTION 3: MANUFACTURE

The vent tubes shall be fabricated from steel plate to form a tube to the following dimensions:

Outside diameter	305 mm
Wall thickness	3.5 mm
Length	15 metres

The manufacture of the tubes shall be in accordance with AS 1579 except that hydrostatic testing is not required. The tubes shall be manufactured by spiral butt welding coiled feedstock and shall conform to the relevant requirements of AS/NZS 1554. The external weld shall be ground flush with the outer surface for a minimum of 50mm from the bottom end to ensure correct location when tube is installed into base.

SECTION 4: COATING

4.1 Surface Preparation

The surface preparation, both internally and externally, shall be abrasive cleaned in accordance with TS 12 and TS 97.

SA Water	TS55 - Vent-Tubes 2 docx	10 January 2007	Page
5/ Wilder	lequed by: Standarde Manager Networks Infractructure	Uncontrolled on printing	1 of 6
PLANNING & INFRASTRUCTURE	issued by. Standards Manager Networks Initastructure	oncontrolled on printing	4 01 0

4.2. Coating Application

4.2.1 External Surface

The external surface of the tubes shall be coated with Inorganic Zinc Silicate in accordance with TS 12. Acceptable products include:-

- Jotun Jotacote 5 applied at 100 microns DFT.
- Ameron D7 applied at 100 microns DFT.

4.2.2 Internal Surface

The internal surface of the tubes shall be coated with solventless epoxy in accordance with TS 97. One of the following products shall be used:-

- Wattyl Sigmaguard CSF 75 applied at 500 microns DFT.
- Jotun Jotacote 412 applied at 500 microns DFT.

4.2.3 Coating Inspection.

The surface preparation and coating application shall be inspected by a third party coating inspector who is qualified in the inspection of high performance coatings. A qualified inspector shall have attained the Australasian Corrosion Association Coating Inspectors Certificate and shall be able to demonstrate that coating inspection duties have been carried out on a regular basis. Inspection reports shall comply with AS 3894.10, AS 3894.11 and AS 3894.12, 'Site Testing of Protective Coatings' equipment and inspection reports.

For the purposes of this Technical Standard, the term "SA Water's representative" referred to in TS 12 and TS 97 shall mean "The third party coating inspector". At the completion of each production batch, the Inspection Reports shall be forwarded to:

SA Water Infrastructure Standards Unit PO Box 1751 ADELAIDE SA 5001

SECTION 5: QUALITY CONTROL AND ASSURANCE

The manufacturer shall implement and maintain an approved quality control/quality assurance system covering all testing and manufacturing processes, hardware, materials and workmanship used in the manufacture of the vent tubes.

Unless specified otherwise, the minimum quality control and assurance system shall be in accordance with AS/NZS ISO 9001 and shall be in accordance with all standards relevant to the manufacture of the vent tubes.

SA Water	TS55 - Vent-Tubes_2.docx	10 January 2007	Page
	Issued by: Standards Manager Networks Infrastructure	I Incontrolled on printing	5 of 6
PLANNING & INFRASTRUCTURE	issued by. Standards Manager Networks Initastructure	oncontrolled on printing	5010

APPENDIX A REFERENCE DRAWING



SA Water	TS55 - Vent-Tubes_2.docx	10 January 2007	Page
	lequed by: Standarde Manager Networke Infractructure	Uncontrolled on printing	6 of 6
PLANNING & INFRASTRUCTURE	issued by. Standards Manager Networks initiastructure	Uncontrolled on printing	0 01 0